



DR. SPANG

INGENIEURGESELLSCHAFT FÜR BAUWESEN, GEOLOGIE UND UMWELTECHNIK MBH

DEVELOPER

Sächsisches Landesamt für Umwelt und Geologie

PROJECT

Renovation of waste heap complex 371 into meadow

- Final configuration of the waste heap, including the relevant road, path, waterway and landscape engineering
- Volume totalling 13.7m m³ and a contact area of approx. 67 ha

OUR SERVICES

- External monitoring of the quality of the work to renovate and return the waste heap to use
- Monitoring of execution of the works for conformity with radiation protection limits and compliance with rules of the art for road, waterway and landscape engineering
- Checks of the redistribution and profiling work, determination of the degrees of compaction, achieved degrees of compaction including permeability coefficients and aggregate gradation, evidence of suitability of the top layers, application of the top layers on the slopes and parts of the plateau and expansion of seepage water catchments

